Hildebrand Farm Near Morgnec c.1820

The three bay long, two story frame dwelling on the Hildebrand Farm was built around 1820 in a vernacular manner, with hall-parlor plan. Both rooms have enclosed winder stairs with closets beneath and vertical beaded board chimney breasts. The two bay, two story wing was constructed soon after the main house. The building is loosely related in form and plan to the miller's house at Urieville, on the property across Morgan Creek, about a half mile away.

Hildebrand Farm received its name from Grace E. Brooks who married Merrill Hildebrand. After her father, P. A. M. Brooks, died in 1934, the farm was transferred to Grace Hildebrand. Prior to that time, the farm was in the ownership of the Brooks family and appears to have accompanied the northern portion of Thornton since the 18th Century. G. M. Brooks appears as owner of the farm on the 1860 map. He was residing at Thornton at the time. On the same map, School No. 4 is located on the Hildebrand Farm opposite the lane to Thornton.

1. Land Records, Lib. RAS 30, fol. 543.

HILDEBRAND FARM Kennedyville, Maryland (ca 1800)

The Hildebrand House is significant as an example of a vernacular farm house of the early 19th century. The main house is a frame structure three bays long and two bays deep. Two stories in height, the building is covered with a 90° gable roof without dormers. Adjacent to the main house is a small two-story kitchen wing. Now greatly altered, the house is similiar in size and plan type to two nearby houses; Massey Farm (K-380), and the Urieville Miller's House (K-291).

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

| NAME | | | | |
|---------------------------------|-----------------------|---|-------------------------------|---------------------------------------|
| HISTORIC HIL | DEBRAND FARM | | | |
| AND/OR COMMON | | | | |
| | | | | |
| LOCATION | East side Perkins | Hill Road, % mile s | south | |
| STREET & NUMBER | of junction with N | Wallis Bros. Road | | |
| CITY, TOWN | | | First CONGRESSIONAL DISTRI | СТ |
| Kenn | edyville | X VICINITY OF | Kent | |
| STATE Mary | land 21645 | | COUNTY | |
| CLASSIFIC | | | | · · · |
| CATEGORY | OWNERSHIP | STATUS | PRESI | ENT USE |
| DISTRICT | PUBLIC | *_OCCUPIED | AGRICULTURE | MUSEUM |
| ∡ BUILDING(S) | X_PRIVATE | UNOCCUPIED | COMMERCIAL | PARK |
| STRUCTURE | BOTH | WORK IN PROGRESS | EDUCATIONAL | X.PRIVATE RESIDENCE |
| SITE | PUBLIC ACQUISITIO | | ENTERTAINMENT | RELIGIOUS |
| OBJECT | IN PROCESS | YES: RESTRICTED | GOVERNMENT | SCIENTIFICTRANSPORTATION |
| | BEING CONSIDERED | YES: UNRESTRICTED NO | INDUSTRIAL MILITARY | OTHER |
| | FPROPERTY ildebrand | v - v - v - v - v - v - v - v - v - v - | Telephone #: unl | isted |
| STREET & NUMBER 8505 Sp | ringvale Lane | | Terephone #. | |
| CITY, TOWN | | | STATE , Z | ip code |
| Silver | Spring _ | VICINITY OF | Maryland | |
| LOCATION | OF LEGAL DESC | CRIPTION | Liber #: RAS | 30 |
| COURTHOUSE. | | | Folio #: 543 | 30 |
| REGISTRY OF DEEDS, | ETC. Kent County Cou. | rt House | | |
| STREET & NUMBER | | | | |
| CITY, TOWN | Chestertown, Ma | ryland 21620 | STATE | |
| REPRESEN | TATION IN EXIS | TING SURVEYS | | |
| TITLE | Historical Trust, S | | , | |
| DATE | | | | · · · · · · · · · · · · · · · · · · · |
| 1968 | | FEDERAL 2 | CSTATE _COUNTY _LOCAL | |
| DEPOSITORY FOR SURVEY RECORDS M | aryland Historical | Trust, The Shaw Hous | se, 21 State Circle | |
| CITY, TOWN | - | 21401 | STATE | |
| | | 27.107 | | |



K-194

CONDITION

__EXCELLENT

¥GOOD

__FAIR

__DETERIORATED

__RUINS
__UNEXPOSED

CHECK ONE

__UNALTERED

CHECK ONE

∠ORIGINAL SITE

_MOVED DATE_____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Hildebrand Farm House is situated in open fields on high ground between two tributaries of Morgan Creek.

The main house is a frame structure three bays long and two bays deep. Two stories in height, the building is covered with a 900 gable roof without dormers. East of the main house is a two-bay long, two-bay deep wing. Also two stories in height and covered by a gable roof, the wing is about two feet lower than the main house. The roofs of both sections of the building are finished with verge boards at the gables and box cornices at the eaves. They are covered with asphalt shingles.

The house rests on a stuccoed brick foundation, and on the west gable, the chimney back is exposed to the second floor joists.

The building is currently undergoing an extensive remodeling which includes replacing all windows, removal or rebuilding of chimmeys, replacing most interior finishes, covering the exterior of the building with narrow aluminum siding, and construction of a screened porch at the east end of the house. A new six-panel door with denticulated architrave replaces the original door and transom on the south facade of the house. A three-part picture window has been installed in the south wall, first floor of the wing.

The house was a typical hall and parlour house common in this area in the eighteenth and early nineteenth centuries. Its floor plan has been altered but simple paneling remains in the gable ends of

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

K-194

| SPECIFIC DAT | ES _{Ca} 1800 | BUILDER/ARCH | AITECT | |
|---------------------|------------------------|-------------------------|-------------------------|----------------------|
| | | INVENTION | | |
| _1900- | COMMUNICATIONS | INDUSTRY | POLITICS/GOVERNMENT | _OTHER (SPECIFY) |
| x _1800-1899 | COMMERCE | EXPLORATION/SETTLEMENT | PHILOSOPHY | _TRANSPORTATION |
| _1700-1799 | ART | ENGINEERING | MUSIC | THEATER |
| _1600-1699 | ★ARCHITECTURE | EDUCATION | MILITARY | _SOCIAL/HUMANITARIAN |
| 1500-1599 | AGRICULTURE | ECONOMICS | LITERATURE | SCULPTURE |
| 1400-1499 | ARCHEOLOGY-HISTORIC | CONSERVATION | LAW | SCIENCE |
| PREHISTORIC | ARCHEOLOGY-PREHISTORIC | COMMUNITY PLANNING | _LANDSCAPE ARCHITECTURE | RELIGION |
| PERIOD | AF | REAS OF SIGNIFICANCE CH | IECK AND JUSTIFY BELOW | |

STATEMENT OF SIGNIFICANCE

This house is significant as an example of a vernacular farm house of the early 19th century. Although greatly altered, it survives as a document of early farm life on this part of the Eastern Shore.

The house is similiar in size and plan type to other nearby houses: the Massey Farm (K-380), and the Urieville Miller's House (K-291). The two houses are similiar in size, have side wings, and hall and parlour floor plans. They probably typify the modest housing that was affordable by small farmers and rural tradesmen.

The barns and corn cribs on the Hildebrand Farm are interesting and well maintained examples of the kind of farm buildings constructed from the late 19th to the early 20th century. It is interesting to note the similiarity between the framing system of the house (ca 1800-1825) and the barns (ca 1875-1925).

K-194

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Maryland Historical Trust Survey Records, K-194, September 12, 1968

| CONTINUE ON SEPARATE SHEET | LF NECESSARI | |
|--|------------------------|---|
| GEOGRAPHICAL DATA | | |
| ACREAGE OF NOMINATED PROPERTY | | |
| | | |
| | | |
| | | |
| | | |
| VERBAL BOUNDARY DESCRIPTION | | * |
| | | |
| | | • |
| | | |
| | | |
| | | |
| LIST ALL STATES AND COUNTIES FOR I | PROPERTIES OVERLAPPING | STATE OR COUNTY BOUNDARIES |
| | | |
| STATE | COUNTY | |
| STATE | COUNTY | |
| | | |
| FORM PREPARED BY | | |
| NAME / TITLE | | |
| Marsha L. Fritz, Survey | Consultant | |
| ORGANIZATION Kent County Planning Com | mmission | DATE 778-4600 ext.67 |
| STREET & NUMBER | | TELEPHONE |
| Court House | | TELETHORE |
| CITY OR TOWN | | STATE |
| Chestertown, Maryland 2 | 21620 | |

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust

The Shaw House, 21 State Circle

Annapolis, Maryland 21401


(301) 267-1438

the first floor rooms.

In both of these rooms, the wooden paneling consists of a door to a corner stair, a door to a closet under the stair, and boarding on the chimney breast. Doors have six raised and beveled panels with a plain ovolo panel moulding. Board paneling consists of random width boards with 3/8" beads. The surrounds of doors and fireplaces are quarterrounds. The fireplace openings are rectangular although the fireplaces themselves have been rebuilt.

Because of ongoing construction, the heavy timber frame of the main house is exposed in some locations. Also visible is the pit-sawn back face of the original weatherboarding which continues around to the east gable of the main house, showing that it predates the wing. Portions of narrow beaded board closets remain on the second story. Original flooring in the building is wide yellow pine.

The outbuildings on the property all appear to date from the later nineteenth or early twentieth century. They are typically frame with pegged frames of heavy timbers, nailed rafters, and vertical siding. Major buildings include barns and corn cribs.



3/32"=1'0"

Form 10-445 | 1. STATE Maryland Kent COUNTY

TOWN Chestertown VICINITY LOrgnec STREET NO. Perkins Hill Road, 1 mile south 2. NAME Hildebrand Farm of Rt. 213, (east)

ORIGINAL OWNER ORIGINAL USE dwelling PRESENT OWNER Mrs. F.M. Hildebrand PRESENT USE tenant nouse WALL CONSTRUCTION frame NO. OF STORIES TWO

HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY K - 194

DATE OR PERIOD early 19th century STYLE Federal ARCHITECT BUILDER

3. FOR LIBRARY OF CONGRESS USE

4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION

OPEN TO PUBLICNO

The Hildebrand Farm is a 19th century structure with proportions and some detail carried over from the \$8th century style of building. It is a two story frame structure, built on a brick foundation, covered with brown shingles, having an "A" roof with a brick chimney on each gable. The back of the brick fireplace on the west gable is exposed to the height of the second floor joists. A very plain door with transom is located off-center between two windows, which have 6/6 sash, white trim and no shutters. On the east side is a two bay long, two story wing with a leanto and a porch on the north side. It is well maintained by the present tenants.

5. PHYSICAL CONDITION OF STRUCTURE Endangered good Interior Exterior

6. LOCATION MAP (Plan Optional)

3. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC.

7. PHOTOGRAPH

9. NAME, ADDRESS AND TITLE OF RECORDER

Michael Bourne

DATE OF RECORD Sept. 12, 1968

| Name Hildebrand Farm | рни | :# K-194 |
|--|---|-----------------------|
| Location Kent COUNTY | · Keurs town | hyville |
| Perkins Hill Road - 1 min | | |
| First owner of record | | DATE |
| Present owner Wws. F.M. Hildebrane | 0 | DATE |
| Address Chastertown, Md. | | |
| Parcel or Deed # | | |
| Original use duelling | | |
| Present use develling -tenant | | |
| Md. Map Coordinates | | |
| Long. & Lat. reading | | |
| Style Federal | | |
| Date(s) of construction early 19th Con | tung | |
| Architect | | |
| Builder | | |
| DESCRIPTION: | | |
| | type wall constru | a shingle |
| | type wall constru | action |
| Foundation-basement brich - | | |
| | | |
| | 0 1 0 | |
| Wall construction - From Co | used w wood | Shuyls |
| | | l- erecential to well |
| Water table, string course, other | | k essentiat to warr |
| | a man dana dana dana tama tama dana dana dana dana dana danah danah danah danah danah | |
| 0 | , , | 0 |
| chimneys in each goods both | - Wist tuepla | e both exposed |
| to I law level | | |

| e Hildebrand Farm | MHT# K-194 |
|---|---------------|
| Entrance type & placement on center - | veny plain |
| Windows 1/6 - 3 bays lang & 16 | cy des |
| Shutters Wo | |
| Roof type A Cornice, eaves wood - good condul | covering wood |
| Dormers, cupolas MD | |
| | |
| Porches on le N. sich y win | |
| Porches on be N. sich y wing Wings, hyphens 2 bay - 2 storm 7- leado hitch. | s" roy - also |
| Wings, hyphens 2 bay - 2 ston 7 | s" roy - also |
| Wings, hyphens 2 bay - 2 ston 7 | |
| Wings, hyphens 2 bay - 2 star 7 leads hitch. Interior: | |
| Wings, hyphens 2 bay - 2 stary / least hitch. Interior: Stairway — | |


| | page 3 |
|--|--|
| Name Hildebrand Fann | MHT# K-194 |
| Physical condition Good Environment fam. | |
| References: MHT Color slide # | |
| MHT B & W # | |
| Owner contacted feach - mrs. Clark OTHER: | |
| Recorder Michael Bourne | |
| Date Sept 12, 1908 | |
| Summary: fle Holdbrand Farm is a 19th Centu | ny streetme wide |
| proportion and som detail carried over for | - Lew 18th Century, this |
| proportion and som detail carried over from style of lendeding. It is a 2 story from brown shingles, havin an "A" rog with a bring the back of the being hiplan under wat gable is end had poists. It very plain door with house between 2 windows, which have to say, while | x chiny on each gath, xposed to the hunt g |

Enclosures: e.g. Map, Historical significance, sketch of floor plan, and angle of photos, etc.

In the lest side is a . 2 boay long, 2 stony wing with a least and

Our posts on the sorter sich. It is well martained by the present

tenants.





11-194

J. Tyles Campbell
FRIE-LENGE MINISTERIOR CHARLES

MARYLAND HISTORICAL TRUST

K-194 Hildebrand Form C.1820

South Facade

HILDEBRAND FARM (K-194)

Kennedyville, Kent County

Photograph: M.L. Fritz, January 1980